



## 12x20 Gibraltar Material List

### Floor- Hemlock

2-6x6x20' Skids  
13-2x6x12'-Joists  
7-2x6x8' Rim Joist, Blocking  
  
1-1x8x12' Porch Flooring-Hemlock  
1-1x8x10'-Porch Flooring-Hemlock  
  
7-1x6x12' Porch Flooring-Hemlock  
7-1x6x10' Porch Flooring-Hemlock

### Walls-Hemlock

10-4x4x12' Beams/ Angle braces  
8-4x4x8' Post/ Beams  
  
2-2x4x14'-Nailers  
6-2x4x10'-Nailers

### Roof-Hemlock

2-2x6x12' Rafters  
16-2x6x10' Rafters  
6-1x4x12' Roof Strapping  
6-1x4x8' Roof Strapping  
2-1x6x12' Ledger Board  
4-1x6x12' Collar Ties  
1-1x6x6' Collar Ties  
1-1x8x16' Ridge Pole  
1-1x8x10' Ridge Pole  
2-1x8x8' Ledger boards  
2-1x10x10' Roof Sheathing  
10-1x12x10' Roof Sheathing  
10-1x12x8' Roof Sheathing

### Temp Bracing/ Extra Lumber

1-2x8x10' Pine  
2-2x4x12'-Pine  
2-1x12x12'-Pine  
3-1x4x12'-Pine  
1-1x4x10'-Pine  
1-1x4x8'-Pine  
1-2x8x10'-Rip for Battens

### Interior

3-1x10x8' Pine  
1-1x4x14'-Pine  
3-1x4x8'-Hemlock  
1-2x4x6' Hemlock

### Siding-Pine

2-1x12x16'  
10-1x12x14''  
22-1x12x10'  
2-1x10x10'  
3-1x8x10'  
2-1x8x8'  
**Battens--Pine- rip to 3/4"**  
3-2x8x12'  
4-2x8x10'  
3-2x8x8'

### Trim-Pine

3-2x8x16' Fascia  
1-2x8x12' Fascia  
1-2x8x10' Fascia  
  
3-2x4x16' Shadow  
2-2x4x12' Shadow  
1-2x4x10' Shadow  
  
2-1x4x16' Window Door,Corner  
4-1x4x14' Window Door,Corner  
1-1x4x12' Window Door,Corner  
3-1x4x10' Window,Door Corner  
3-1x4x8' Window,Door,Corner  
10-2x4x8' Arch Bottom  
  
1-1x4x10'-rip to 1x2 -Door stops  
2-1x6x10' Rip to 1x3 Window Stops  
1-1x10x10' Rip to 1x5 Door Casing



## **12x20 Gibraltar Mill Work & Hardware**

### **Millwork**

4-Barn Sash Windows-3x2  
1-JCS 2-8 Door- 32x80.5 with 16x21 window  
1- Louvered Vent  
1-16" Vent Batten

### **Hardware**

10lbs-16D Framing Nails  
5lbs-16D Galv Nails for trim  
12lbs-8D HDG Hand Nails  
3lbs-6D HDG Hand Nails  
600-Roofing Screws  
  
1-1/4" Hex Bit  
1-#2 Square Drive Bit  
  
12 Window Hinges-Black  
48-Window Hinge Screws  
4-Window Hooks & Eyes  
  
3- 8" Black Door Hinges  
30-Black Door Hinge Screws

### **Flooring Lumber**

7 -3/4" 4x8 CDX Plywood- Flooring  
3--3/4" 4x8 CDX Plywood-Arch Framing

### **Corrugated Roofing**

7-Pieces of Roofing @ 89"  
4-Pieces of Roofing @ 91"  
2-Pieces of Roofing @ 80.75"  
2-Pieces of Roofing @ 59.5"  
2-Pieces of Roofing @ 40.5"  
2-Pieces of Roofing @ 19.5"  
4-Pieces of Roofing @ 11"

2-Piece of Ridge Cap @ 126"  
1-Pieces Ridge Cap @79"  
1-Pieces Ridge Cap @16"

### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips



## 12x20 Gibraltar- 8 Ft Walls

### Material List

#### Floor- Hemlock

2-6x6x20' Skids  
13-2x6x12'-Joists  
7-2x6x8' Rim Joist, Blocking  
  
1-1x8x12' Porch Flooring-Hemlock  
1-1x8x10'-Porch Flooring-Hemlock  
  
7-1x6x12' Porch Flooring-Hemlock  
7-1x6x10' Porch Flooring-Hemlock

#### Walls-Hemlock

2-4x4x12' Beams/ Angle braces  
5-4x4x10'  
12-4x4x8' Post/ Beams  
2-2x4x12'-Nailers  
4-2x4x10'-Nailers  
9-2x4x8'

#### Roof-Hemlock

2-2x6x12' Rafters  
16-2x6x10' Rafters  
6-1x4x12' Roof Strapping  
6-1x4x8' Roof Strapping  
2-1x6x12' Ledger Board  
4-1x6x12' Collar Ties  
1-1x6x6' Collar Ties  
1-1x8x16' Ridge Pole  
1-1x8x10' Ridge Pole  
2-1x8x8' Ledger boards  
2-1x10x10' Roof Sheathing  
10-1x12x10' Roof Sheathing  
10-1x12x8' Roof Sheathing

#### Temp Bracing/ Extra Lumber

1-2x8x10' Pine  
2-2x4x12'-Pine  
2-1x12x12'-Pine  
3-1x4x12'-Hemlock  
2-1x4x14'-Hemlock  
1-1x4x8'-Hemlock  
1-2x8x10' Pine -Rip for Battens

#### Interior

3-1x10x8' Pine  
1-1x4x14'-Pine  
3-1x4x8'-Hemlock  
1-2x4x6' Hemlock

#### Siding-Pine

5-1x12x14'  
13-1x12x12'  
26-1x12x8'  
2-1x10x12'  
4-1x8x12'  
**Battens--Pine- rip to 3/4"**  
2-2x8x14'  
4-2x8x12'  
4-2x8x10'  
3-2x8x8'

#### Trim-Pine

3-2x8x16' Fascia  
1-2x8x12' Fascia  
1-2x8x10' Fascia  
  
3-2x4x16' Shadow  
2-2x4x12' Shadow  
1-2x4x10' Shadow  
  
2-1x4x16' Window Door,Corner  
4-1x4x14' Window Door,Corner  
1-1x4x12' Window Door,Corner  
4-1x4x10' Window,Door Corner  
4-1x4x8' Window,Door,Corner  
10-2x4x8' Arch Bottom  
  
1-1x4x10'-rip to 1x2 -Door stops  
2-1x6x10' Rip to 1x3 Window Stops  
1-1x10x10' Rip to 1x5 Door Casing



## **12x20 Gibraltar- 8 Ft Walls Mill Work & Hardware**

### **Millwork**

4-Barn Sash Windows-3x2  
1-JCS 3-0 Door- 36x80.5 with 16x21 window  
1- Louvered Vent  
1-16" Vent Batten

### **Hardware**

10bs-16D Framing Nails  
5lbs-16D Galv Nails for trim  
12lbs-8D HDG Hand Nails  
3lbs-6D HDG Hand Nails  
600-Roofing Screws  
  
1-1/4" Hex Bit  
1-#2 Square Drive Bit  
  
12 Window Hinges-Black  
48-Window Hinge Screws  
4-Window Hooks & Eyes  
  
3- 8" Black Door Hinges  
30-Black Door Hinge Screws

### **Flooring Lumber**

7 -3/4" 4x8 CDX Plywood- Flooring  
3--3/4" 4x8 CDX Plywood-Arch Framing

### **Corrugated Roofing**

7-Pieces of Roofing @ 89"  
4-Pieces of Roofing @ 91"  
2-Pieces of Roofing @ 80.75"  
2-Pieces of Roofing @ 59.5"  
2-Pieces of Roofing @ 40.5"  
2-Pieces of Roofing @ 19.5"  
4-Pieces of Roofing @ 11"  
  
2-Piece of Ridge Cap @ 126"  
1-Pieces Ridge Cap @79"  
1-Pieces Ridge Cap @16"

### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips



## 14x20 Gibraltar Material List

### Floor- Hemlock

2-6x6x20' Skids  
11-2x6x14' Joists  
7-2x6x12' Rim Joists  
2-2x6x8' Rim Joists

1-1x8x12' Porch Flooring-Hemlock  
1-1x8x10'-Porch Flooring-Hemlock  
7-1x6x12' Porch Flooring-Hemlock  
7-1x6x10' Porch Flooring-Hemlock

### Walls-Hemlock

8-4x4x12' Beams/ Angle braces  
3-4x4x10' Post/ Beams  
4-4x4x8' Post

1-2x4x12'-Nailers  
6-2x4x10'-Nailers  
6-2x4x8'-Nailers

### Roof-Hemlock

2-1x8x10' Ridge Pole  
1-1x8x8'

2-2x6x16' Rafters  
11-2x6x12' Rafters  
5-2x6x8' Rafters

2-2x8x8; Ledger Board  
2-1x12x12' Ledger Board  
10-1x12x10' Roof Sheathing  
10-1x12x8' Roof Sheathing  
2-1x10x8' Roof Sheathing  
4-1x6x12' Collar Ties  
1-1x6x6' Collar Ties  
6-1x4x12' Roof Strapping  
6-1x4x8' Roof Strapping

### Temp Bracing/ Extra Lumber

4-1x4x12' Hemlock  
1-2x4x14' Hemlock  
1-1x12x14'-Pine  
1-2x8x8' Rip for Battens

### Interior

3-1x10x10' Pine  
1-1x4x14'-Pine  
3-1x4x10'-Hemlock  
1-2x4x6' Hemlock

### Siding-Pine

1-1x12x16'  
10-1x12x14'  
4-1x12x12'  
10-1x12x10'  
11-1x12x8'  
5-1x10x10'  
3-1x10x8'  
3-1x8x8'

### **Battens--Pine- rip to 3/4"**

2-2x8x14'  
2-2x8x12'  
3-2x8x10'  
1-2x8x8'

### Trim-Pine

3-2x8x12' Fascia  
2-2x8x10' Fascia  
3-2x8x8' Fascia

2-2x4x16' Shadow  
4-2x4x12' Shadow  
2-2x4x10' Shadow

2-1x4x16' Window ,Door , Corner  
2-1x4x14' Window ,Door , Corner  
1-1x4x12' Window ,Door , Corner  
2-1x4x10' Window ,Door , Corner

10-2x4x8' Arch Bottom

2-1x6x10' Rip to 1x3 Window Stops  
1-1x10x10' Rip to 1x5 Door Casing



## **14x20 Gibraltar Mill Work & Hardware**

### **Millwork**

4-Barn Sash Windows-3x2  
1-JCS 2-8 Door- 32x80.5 with 16x21 window  
1- Louvered Vent  
1-16" Vent Batten

### **Hardware**

10lbs-16D Framing Nails  
5lbs-16D Galv Nails for trim  
12lbs-8D HDG Hand Nails  
3lbs-6D HDG Hand Nails  
600-Roofing Screws  
  
1-1/4" Hex Bit  
1-#2 Square Drive Bit  
  
12 Window Hinges-Black  
48-Window Hinge Screws  
4-Window Hooks & Eyes  
  
3- 8" Black Door Hinges  
30-Black Door Hinge Screws

### **Flooring Lumber**

7 -3/4" 4x8 CDX Plywood- Flooring  
3--3/4" 4x8 CDX Plywood-Arch Framing

### **Corrugated Roofing**

7-Pieces of Roofing @ 99"  
2-Pieces of Roofing @ 102"  
2-Pieces of Roofing @ 98"  
2-Pieces of Roofing @ 59"  
2-Pieces of Roofing @ 21"  
2-Pieces of Roofing @ 89"  
2-Pieces of Roofing @ 50"  
2-Pieces of Roofing @ 11"  
4-Pieces of Roofing @ 9"  
  
2-Piece of Ridge Cap @ 126"  
1-Pieces Ridge Cap @93"  
1-Pieces Ridge Cap @16"

### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips



## 14x20 Gibraltar- 8ft Walls

### Material List

#### Floor- Hemlock

2-6x6x20' Skids  
11-2x6x14' Joists  
7-2x6x12' Rim Joists  
2-2x6x8' Rim Joists

1-1x8x12' Porch Flooring-Hemlock  
1-1x8x10'-Porch Flooring-Hemlock  
7-1x6x12' Porch Flooring-Hemlock  
7-1x6x10' Porch Flooring-Hemlock

#### Walls-Hemlock

6-4x4x12' Beams/ Angle braces  
7-4x4x10' Post/ Beams  
9-4x4x8' Post

1-2x4x12'-Nailers  
6-2x4x10'-Nailers  
6-2x4x8'-Nailers

#### Roof-Hemlock

2-1x8x10' Ridge Pole  
1-1x8x8'

2-2x6x16' Rafters  
11-2x6x12' Rafters  
5-2x6x8' Rafters

2-1x8x8; Ledger Board  
2-1x12x12' Ledger Board  
10-1x12x10' Roof Sheathing  
10-1x12x8' Roof Sheathing  
2-1x10x8' Roof Sheathing  
4-1x6x12' Collar Ties  
1-1x6x6' Collar Ties  
6-1x4x12' Roof Strapping  
6-1x4x8' Roof Strapping

#### Temp Bracing/ Extra Lumber

3-1x4x14' Hemlock  
1-2x6x14' Hemlock  
1-2x4x12' Hemlock  
1-1x12x14'-Pine  
1-2x8x8' Pine-Rip for Battens

#### Interior

3-1x10x10' Pine  
1-1x4x14'-Pine  
3-1x4x10'-Hemlock  
1-2x4x6' Hemlock

#### Siding-Pine

10-1x12x12'  
38-1x12x10'  
3-1x12x8'  
3-1x10x12'  
1-1x10x10'  
3-1x10x8'  
1-1x8x12'  
4-1x8x10'

#### **Battens--Pine- rip to 3/4"**

1-2x8x16'  
4-2x8x12'  
6-2x8x10'  
2-2x8x8'

#### Trim-Pine

3-2x8x12' Fascia  
2-2x8x10' Fascia  
3-2x8x8' Fascia

6-2x4x12' Shadow  
4-2x4x8' Shadow

1-1x4x12' Window, Door, Corner  
10-1x4x10' Window, Door, Corner  
6-1x4x8' Window, Door, Corner

2-1x6x10' Rip to 1x3 Window Stops  
1-1x10x10' Rip to 1x5 Door Casing



## **14x20 Gibraltar- 8ft Walls Mill Work & Hardware**

### **Millwork**

4-Barn Sash Windows-3x2  
  
1-JCS 3-0 Door- 36x80.5 with 16x21 window  
1- Louvered Vent  
    1-16" Vent Batten

### **Hardware**

10lbs-16D Framing Nails  
5lbs-16D Galv Nails for trim  
12lbs-8D HDG Hand Nails  
3lbs-6D HDG Hand Nails  
600-Roofing Screws  
  
1-1/4" Hex Bit  
1-#2 Square Drive Bit  
  
12 Window Hinges-Black  
48-Window Hinge Screws  
4-Window Hooks & Eyes  
  
3- 8" Black Door Hinges  
30-Black Door Hinge Screws

### **Flooring Lumber**

7 -3/4" 4x8 CDX Plywood- Flooring  
3--3/4" 4x8 CDX Plywood-Arch Framing

### **Corrugated Roofing**

7-Pieces of Roofing @ 99"  
2-Pieces of Roofing @ 102"  
2-Pieces of Roofing @ 98"  
2-Pieces of Roofing @ 59"  
2-Pieces of Roofing @ 21"  
2-Pieces of Roofing @ 89"  
2-Pieces of Roofing @ 50"  
2-Pieces of Roofing @ 11"  
4-Pieces of Roofing @ 9"  
  
2-Piece of Ridge Cap @ 126"  
1-Pieces Ridge Cap @93"  
1-Pieces Ridge Cap @16"

### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips





## 14x30 Gibraltar Material List

### Floor- Hemlock

10-2x6x16' Skids & Rim Joists  
26-2x6x14' Skids & Floor Joists  
102x6x10' Blocking  
1-1x8x12' Porch Flooring-Hemlock  
2-1x8x10'-Porch Flooring-Hemlock  
7-1x6x12' Porch Flooring-Hemlock  
11-1x6x10' Porch Flooring-Hemlock  
4-1x6x8'

### Walls-Hemlock

1-4x4x16' Posts  
8-4x4x14' Posts & Beams  
10-4x4x12' Braces & Posts  
4-4x4x10' Beams  
5-2x4x14' Window Sills  
12-2x4x10' Nailers  
1-2x4x8 Header

### Roof-Hemlock

9-2x6x10' Rafters  
27-2x6x8' Rafters  
3-1x12x14' Sheathing  
4-1x12x10' Sheathing  
2-1x12x8' Sheathing  
4-1x10x14' Sheathing-PINE  
4-1x10x10' Sheathing-PINE  
2-1x8x14' Ledger Boards  
3-1x8x10' Ridge Poles  
1-1x8x8' Ridge Pole  
7-1x6x12' Collar Ties  
10-1x4x12' Strapping  
6-1x4x10' Strapping

### Temp Bracing/ Extra Lumber

8-1x4x10' Hemlock  
1-2x4x16' Hemlock  
1-2x6x14' Hemlock  
1-1x12x16'-Pine

### Interior

3-1x10x10' Pine  
1-1x4x14'-Pine  
3-1x4x10'-Hemlock  
1-2x4x6' Hemlock

### Siding-Pine

15-1x12x14'  
8-1x12x12'  
5-1x12x10'  
21-1x12x8'  
1-1x10x12'  
4-1x10x8'  
2-1x8x8'  
1-1x6x6'  
**Battens--Pine- rip to 3/4"**  
3-2x8x14'  
4-2x8x10'  
7-2x8x8'

### Trim-Pine

2-2x8x14' Fascia  
4-2x8x12' Fascia  
5-2x8x10' Fascia  
  
2-2x4x14' Shadow  
2-2x4x12' Shadow  
6-2x4x10' Shadow  
1-1x6x12' Porch Trim  
1-1x6x10' Porch Trim  
  
4-1x4x14' Window ,Door , Corner  
4-1x4x10' Window ,Door , Corner  
6-1x4x8' Window ,Door , Corner  
  
10-2x4x8' Arch Bottom  
1-1x10x10' Rip to 5" Door Casing  
1-1x10x8' Rip to 5" Corner Trim  
3-1x6x10' Rip to 3" Window Stops  
1-1x4x10' Rip to 2" Door Stops



## 14x30 Gibraltar

### Mill Work & Hardware

#### Millwork

6-Barn Sash Windows-3x2  
1-JCS 2-8 Door-(C)  
32x80.5 with 16x21 window  
1- Louvered Vent  
1-16" Vent Batten  
4-3/4" CDX Plywood Arch Templates-A  
2-3/4" CDX Plywood Arch Templates-B  
2 PCS 1x4 Arch Trim

#### Corrugated Roofing

11-Pieces of Roofing @ 97"  
6-Pieces of Roofing @ 100"  
2-Pieces of Roofing @ 90"  
2-Pieces of Roofing @ 80"  
2-Pieces of Roofing @ 50"  
2-Pieces of Roofing @ 41"  
2-Pieces of Roofing @ 11"  
4-Pieces of Roofing @ 9"  
3-Piece of Ridge Cap @ 126"  
1-Pieces Ridge Cap @92"  
1-Pieces Ridge Cap @48"

#### Hardware

14lbs-16D Framing Nails  
10lbs-16D HDG Hand Nails  
16lbs-8D HDG Hand Nails  
8lbs-6D HDG Hand Nails  
1000-Roofing Screws  
  
1-1/4" Hex Bit  
1-#2 Square Drive Bit  
  
18 Window Hinges-Black  
75-Window Hinge Screws  
8-Window Hooks & Eyes  
  
3- 8" Black Door Hinges  
30-Black Door Hinge Screws  
1 - Black Thumb Latch  
  
2PCS ALuminum Flashing-144"  
2PCS ALuminum Flashing-64"

#### Suggested Tools

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips

#### Flooring

10 -3/4" 4x8 CDX Plywood- Flooring



## 14x40 Gibraltar Material List

### Floor- Hemlock

33-2x6x14'  
10-2x6x12'  
18-2x6x10'  
4-2x6x8'  
2-1x8x12'  
2-1x8x10'  
4-1x6x14'  
6-1x6x12'  
14-1x6x10'  
4-1x6x8'

### Walls-Hemlock

6-4x4x14'  
11-4x4x12'  
10-4x4x10'  
2-4x4x8'  
6-2x4x14'  
12-2x4x10'

### Roof-Hemlock

23-2x6x8'  
21-2x6x10'  
1-1x12x14'  
5-1x12x12'  
1-1x12x8'  
8-1x10x12'  
2-1x8x14'  
1-1x8x12'  
2-1x8x10'  
3-1x8x8'  
16-1x4x14'  
13-1x4x12'

### Temp Bracing/ Extra Lumber

4-1x4x12' Hemlock  
2-1x4x10'  
2-1x4x8'  
1-2x4x14' Hemlock  
1-2x6x14' Hemlock  
1-1x12x14'-Pine

### Interior

3-1x10x10' Pine  
1-1x4x14'-Pine  
3-1x4x10'-Hemlock  
1-2x4x6' Hemlock

### Siding-Pine

6-1x8x8'  
1-1x10x8'  
2-1x10x10'  
1-1x10x12'  
64-1x12x8'  
13-1x12x10'  
9-1x12x12'  
  
5-2x8x10' Rip to 3/4"  
13-2x8x8' Rip to 3/4"

### Trim-Pine

4-2x8x12'  
10-2x8x10'  
3-2x4x14'  
4-2x4x12'  
5-2x4x10'  
10-2x4x8' Arch Bottom  
  
2-1x4x14'  
4-1x4x12'  
4-1x4x10'  
2-1x4x8'  
  
1-1x10x10' Rip to 1x5 Door Casing  
4-1x6x16' Rip to 1x3 Window Stops  
1-1x10x10' Rip to 1x5 Door Casing  
1-1x4x10' Rip to 2"



## 14x40 Gibraltar Mill Work & Hardware

### Millwork

4-Barn Sash Windows-4x2  
2-Barn Sash Windows-3x2  
JCS 2-8 Door- 32x80.5 with 16x21 window  
1- Louvered Vent  
1-16" Vent Batten

### Corrugated Roofing

16-Pieces of Roofing @ 97"  
14-Pieces of Roofing @ 102"  
4-Pieces of Roofing @ 9"  
  
4-Piece of Ridge Cap @ 126"  
1-Pieces Ridge Cap @92"  
1-Pieces Ridge Cap @48"

### Hardware

20bs-16D Framing Nails 12lbs-16D Galv Nails  
for trim  
12lbs-8D HDG Hand Nails  
10lbs-6D HDG Hand Nails  
1200-Roofing Screws  
  
1-1/4" Hex Bit  
1-#2 Square Drive Bit  
  
18 Window Hinges-Black  
74-Window Hinge Screws  
12-Window Hooks & Eyes  
  
3- 8" Black Door Hinges  
30-Black Door Hinge Screws

### Suggested Tools

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips

### Flooring Lumber

13 -3/4" 4x8 CDX Plywood- Flooring  
3--3/4" 4x8 CDX Plywood-Arch Framing