



12x20 Gibraltar-8 Ft Walls-4 Season

Material List

Floor

4-2x6x16' Skids-Hemlock
8-2x6x12' Skids-Hemlock
1-2x6x16' Rim-joist-KD Spruce
13-2x6x12' Rim Joist /Floor Joist-KD Spruce
4-2x6x10' Joist Blocking -KD Spruce
1-1x8x12' Porch Decking
1-1x8x10' Porch Decking
7-1x6x12' Porch Decking
7-1x6x10' Porch Decking

Walls-Hemlock

5-4x4x16' Posts & Beams
5-4x4x12' Beams
9-4x4x10' Post & Angle Braces
1-2x6x12' Insulation nailer
1-2x6x10' Insulation nailer
11-2x4x16' Wall Framing & Insulation nailers
2-2x4x14' Wall Framing & Insulation nailers
3-2x4x12' Wall Framing & Insulation nailers
13-2x4x10' Wall Framing & Insulation nailers

Roof

11-2x6x12' KD Spruce-Rafters
5-2x4x8' KD Spruce-Collar Ties

6-2x6x10' Hemlock-Rafters
2-2x4x14' Dormer Rafters
1-2x4x8' Dormer Rafters
4-1x12x16' Pine-Roof Sheathing
2-1x12x14' Pine-Roof Sheathing
6-1x12x6' Pine-Roof Sheathing
12-1x12x12' Pine-Roof Sheathing

1-1x8x16' Pine-Ledger Board
2-1x8x10' Pine- Ridge Pole
1-1x6x14' Hemlock- Dormer Ridge Porch Pad

Exterior Siding-Pine

2-1x12x14'
33-1x12x12'
31-1x12x10'
2-1x6x12'

Interior Siding- Ship-Lap Pine

5-1x12x16'
50-1x12x12'
22-1x12x10'

Battens--Pine- rip to 3/4"

2-2x8x14' Battens
3-2x4x12'
14-2x8x10' Battens

Trim-Pine

3-2x8x16'-Fascia
1-2x8x14'-Fascia
3-2x8x10' Fascia
7-2x4x16' Shadow & Arch
2-2x4x12' Shadow
4-2x4x10' Shadow
3-1x8x10' Corner Trim
2-1x6x12' Porch Trim
1-1x6x8' Porch Trim

10-1x4x16' Window & Door Trim
2-1x4x14'
10-1x4x10'

Temp Bracing/ Extra Lumber

2-2x4x14' Hemlock-Extra
2-1x12x14' Pine- Extra
1-1x12x14'-SHIP-LAP-Extra
2-1x4x14' Hemlock- Temp Braces
2-1x4x12' Hemlock- Temp Braces
1-1x4x8' Hemlock- Temp Braces



12x20 Gibraltar-8 Ft Walls-4 Season

Material List

Floor

4-2x6x16' Skids-Hemlock
8-2x6x12' Skids-Hemlock
1-2x6x16' Rim-joist-KD Spruce
13-2x6x12' Rim Joist /Floor Joist-KD Spruce
4-2x6x10' Joist Blocking -KD Spruce
1-1x8x12' Porch Decking
1-1x8x10' Porch Decking
7-1x6x12' Porch Decking
7-1x6x10' Porch Decking

Walls-Hemlock

5-4x4x16' Posts & Beams
5-4x4x12' Beams
9-4x4x10' Post & Angle Braces
1-2x6x12' Insulation nailer
1-2x6x10' Insulation nailer
11-2x4x16' Wall Framing & Insulation nailers
2-2x4x14' Wall Framing & Insulation nailers
3-2x4x12' Wall Framing & Insulation nailers
13-2x4x10' Wall Framing & Insulation nailers

Roof

11-2x6x12' KD Spruce-Rafters
5-2x4x8' KD Spruce-Collar Ties

6-2x6x10' Hemlock-Rafters
2-2x4x14' Dormer Rafters
1-2x4x8' Dormer Rafters
4-1x12x16' Pine-Roof Sheathing
2-1x12x14' Pine-Roof Sheathing
6-1x12x6' Pine-Roof Sheathing
12-1x12x12' Pine-Roof Sheathing

1-1x8x16' Pine-Ledger Board
2-1x8x10' Pine- Ridge Pole
1-1x6x14' Hemlock- Dormer Ridge Porch Pad

Exterior Siding-Pine

2-1x12x14'
33-1x12x12'
31-1x12x10'
2-1x6x12'

Interior Siding- Ship-Lap Pine

5-1x12x16'
50-1x12x12'
22-1x12x10'

Battens--Pine- rip to 3/4"

2-2x8x14' Battens
3-2x4x12'
14-2x8x10' Battens

Trim-Pine

3-2x8x16'-Fascia
1-2x8x14'-Fascia
3-2x8x10' Fascia
7-2x4x16' Shadow & Arch
2-2x4x12' Shadow
4-2x4x10' Shadow
3-1x8x10' Corner Trim
2-1x6x12' Porch Trim
1-1x6x8' Porch Trim

10-1x4x16' Window & Door Trim
2-1x4x14'
10-1x4x10'

Temp Bracing/ Extra Lumber

2-2x4x14' Hemlock-Extra
2-1x12x14' Pine- Extra
1-1x12x14'-SHIP-LAP-Extra
2-1x4x14' Hemlock- Temp Braces
2-1x4x12' Hemlock- Temp Braces
1-1x4x8' Hemlock- Temp Braces



Jamaica Cottage Shop, Inc. 170 Winhall Station Road S. Londonderry, VT 05155
Voice 802-297-3760 Fax 802-297-2825 plans@JamaicaCottageShop.com

12x20 Gibraltar-8 Ft Walls-4 Season

Mill Work & Hardware

Mill-work

1-3-0x6-8 Nine Lite Steel Door-LHIS
4-3x2 Sliding Insulated Windows

Additional Lumber

6 -3/4" 4x8 CDX Plywood
5 -3/8" 4x8 CDX Plywood

Hardware

10bs-16D Framing Nails-3-1/2"
10bs-16D Galvanized Framing Nails-3-1/2"
20lbs-8D Galvanized Hand Nails
12lbs-6D Galvanized Hand Nails
600-Roofing Screws-1-1/2"

1-1/4" Hex Bit

Locking Door Hardware Kit-H.K.DOOR

Corrugated Roofing

16- Pieces of Roofing @91"
2-Pieces of Ridge Cap @ 126"
1-Pieces of Ridge Cap @ 82"
1-Pieces of Ridge Cap @ 76"

Suggested Tools

Skill Saw or Hand saw Saw-z-all or chain saw
Hammer
Nail puller (cats paw or crow bar)
25' tape measure Chalk line Extension Cord Tin
Snips
Staple gun
Pencil
Speed Square Four-foot level Cordless Drill
1/4" drive bit for drill
#2 Phillips
#3 Square Drive Razor Knife Chisel

Interior

104 Ft of WeatherMate Vapor Barrier
5 Pieces @22' of TRI-FLEX Vapor Barrier
360 SqFt R-21 5-1/2" -24"OC Fiberglass Insulation
24-4x8x1-3/4" Rigid Foam Insulation
Foil Backed
65' of 3" Bituthene Strips
11' of 36"w Bituthene

Cutting will be necessary to complete the kit. Some boards may need to be cut to length. Rough openings for door and window will need to be cut out. Some trim boards may need to be ripped to width.



14x30 Gibraltar-4 Season Material List

Floor

8-2x6x16' -Hemlock-Skids
8-2x6x14' -Hemlock-Skids
7-2x6x16' -KD Spruce-Joists & Blocking
18-2x6x14' -KD Spruce- Joists
1-1x8x12' Hemlock-Porch Decking
2-1x8x10' Hemlock-Porch Decking
2-1x6x16' Hemlock-Porch Decking
4-1x6x14' Hemlock-Porch Decking
3-1x6x12' Hemlock-Porch Decking
11-1x6x10' Hemlock-Porch Decking

Walls-Hemlock

1-4x4x16' Posts & Beams
9-4x4x14' Posts & Beams
9-4x4x12' Beams & Angle Braces
4-4x4x10' Beams
2-2x4x16' Nailers
11-2x4x14' Nailers
7-2x4x12' Nailers
7-2x4x10' Nailers

Roof

12-2x6x16' KD Spruce-Rafters
10-2x4x10' KD Spruce-Collar ties

2-2x6x16' Hemlock-Rafters
8-2x6x10' Hemlock-Porch Rafters

8-1x12x16'-Pine-Roof Sheathing
10-1x12x14' Pine-Roof Sheathing
25-1x12x12' Pine-Roof Sheathing

1-1x8x16' Pine-Ridge Pole
3-1x8x14' Pine-Ridge Pole
1-1x8x8' Pine-Ridge Pole

Exterior Siding-Pine

20-1x12x16'
17-1x12x14'
20-1x12x10'

Interior Sheathing- Ship-Lap Pine

17-1x12x16'
17-1x12x14'
53-1x12x12'
6-1x12x10'

Battens--Pine- rip to 3/4"

8-2x8x12'
10-2x8x8'

Trim-Pine

2-2x8x14' Fascia
4-2x8x12'
5-2x8x10'

2-2x4x14' Shadow
4-2x4x12'
5-2x4x10'

1-1x8x14' :Porch Corner Trim
2-1x6x14' Porch Joist Trim
1-1x6x12'

12-1x4x16' Corner/Door/Window Trim
9-1x4x14'
4-1x4x12'
6-1x4x10'



14x30 Gibraltar-4 Season

Material List

Mill-work

1-3-0x6-8 Nine Lite Steel Door-LHIS
2-4x2 Sliding Insulated Windows
2-3x2 Sliding Insulated Windows
1-2x2 Awning Insulated Windows

Additional Lumber

9 -3/4" 4x8 CDX Plywood
10 -3/8" 4x8 CDX Plywood

Hardware

12bs-16D Framing Nails-3-1/2"
10bs-16D Galvanized Framing Nails-3-1/2"
20lbs-8D Galvanized Hand Nails
12lbs-6D Galvanized Hand Nails
600-Roofing Screws-1-1/2"

1-1/4" Hex Bit

Locking Door Hardware Kit-H.K.DOOR

Corrugated Roofing

21- Pieces of Roofing @100"
3-Pieces of Ridge Cap @ 126"
1-Pieces of Ridge Cap @ 96"
1-Pieces of Ridge Cap @ 48"

Suggested Tools

Skill Saw or Hand saw Saw-z-all or chain saw
Hammer
Nail puller (cats paw or crow bar)
25' tape measure Chalk line Extension Cord Tin Snips
Staple gun
Pencil
Speed Square Four-foot level Cordless Drill
1/4" drive bit for drill
#2 Phillips
#3 Square Drive Razor Knife Chisel

Interior

131 Ft of WeatherMate Vapor Barrier
6 Pieces @32' of TRI-FLEX Vapor Barrier
650 Sq Ft R-21 5-1/2" -24"OC Fiberglass Insulation
24-4x8x1-3/4" Rigid Foam Insulation
Foil Backed
90' of 3" Bituthene Strips
24' of 36" Bituthene Strips

Cutting will be necessary to complete the kit. Some boards may need to be cut to length. Rough openings for door and window will need to be cut out. Some trim boards may need to be ripped to width.