

# **Jamaica Cottage Shop, Inc.** 170 Winhall Station Road S. Londonderry, VT 05155 Voice 802-297-3760 Fax 802-297-2825 plans@JamaicaCottageShop.com

# 12x20 Hobby House-4 Season Material List

#### Floor

1-6x6x14' Treated -Sill

1-6x6x8' Treated -Sill

4-2x6x16' Skids-Hemlock

8-2x6x12' Skids-Hemlock

1-2x6x16' Rim-Joist-KD Spruce

13-2x6x12' Rim Joist /Floor Joist-KD Spruce

4-2x6x10' Joist Blocking -KD Spruce

# Walls-Hemlock

7-4x4x16' Posts & Beams

1-4x4x14' Overhang Beam

8-4x4x12' Angle Braces-Gable Beams

4-4x4x10' Overhang Posts

1-4x4x8' Overhang Beam

4-2x4x16' Wall Framing & Insulation nailers

4-2x4x14' Wall Framing & Insulation nailers

20-2x4x12' Wall Framing & Insulation nailers

19-2x4x10' Wall Framing & Insulation nailers

#### Roof

22-2x6x10' KD Spruce-Rafters

7-2x6x8' KD Spruce-Collar Ties

13-2x6x10' Hemlock-Overhang Rafters

10-1x12x16' Pine-Roof Sheathing

20-1x12x12' Pine-Roof Sheathing

2-1x12x10' Pine -Ledger

1-1x8x12' Pine- Ridge Pole

1-1x8x8' Pine- Ridge Pole

1-1x6x16' Pine-Pad out

### **Exterior Siding-Pine**

8-1x12x16'

8-1x12x14'

8-1x12x12'

42-1x12x10'

1-1x6x12'

4-1x6x10'

## **Interior Siding- Ship-Lap Pine**

17-1x12x16'

8-1x12x14'

26-1x12x12'

56-1x12x10'

## Battens--Pine- rip to 3/4"

2-2x8x14' Battens

5-2x4x12'

14-2x8x10' Battens

# **Trim-Pine**

3-2x8x14'-Fascia

6-2x8x10' Fascia

5-2x4x12' Shadow

4-2x4x10' Shadow

6-1x4x16' Window/ Door Trim

1-1x4x14' Window/Door Trim

4-1x4x12' Window/Door Trim

19-1x4x10' Corner trim /Window Trim

# Temp Bracing/ Extra Lumber

1-2x4x10' Hemlock-Extra

2-1x12x12' Pine- Extra

2-1x12x12'-SHIP-LAP-Extra

6-1x4x12' Hemlock- Temp Braces



# **Jamaica Cottage Shop, Inc.** 170 Winhall Station Road S. Londonderry, VT 05155 Voice 802-297-3760 Fax 802-297-2825 plans@JamaicaCottageShop.com

# 12x20 Hobby House-4 Season Mill Work & Hardware

#### Mill-work

1-3-0x6-8 Nine Lite Steel Door-LHIS

2-4x2 Sliding Insulated Windows

2-3x2 Sliding Insulated Windows

1-2x2 Awning Insulated Windows

#### Hardware

12bs-16D Framing Nails-3-1/2"
10bs-16D Galvanized Framing Nails-3-1/2"
20lbs-8D Galvanized Hand Nails
12lbs-6D Galvanized Hand Nails
600-Roofing Screws-1-1/2"

1-1/4" Hex Bit

Locking Door Hardware Kit-H.K.DOOR

#### Interior

129 Ft of WeatherMate Vapor Barrier
10 Pieces @22' of TRI-FLEX Vapor Barrier
680 SqFt R-21 5-1/2" -24"OC Fiberglass Insulation
22-4x8x1-3/4" Rigid Foam Insulation
Foil Backed
85' of 3" Bituthene Strips
42' of 36" Bituthene Strips

# **Additional Lumber**

8 -3/4" 4x8 CDX Plywood 8 -3/8" 4x8 CDX Plywood

#### **Corrugated Roofing**

- 8- Pieces of Roofing @115"
- 8- Pieces of Roofing @105"
- 8- Pieces of Roofing @67"
- 2-Pieces of Ridge Cap @ 126"
- 1-Pieces of Ridge Cap @ 42"

#### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw Hammer

Nail puller (cats paw or crow bar)

25' tape measure Chalk line Extension Cord Tin Snips

Staple gun

Pencil

Speed Square Four-foot level Cordless Drill

1/4" drive bit for drill

#2 Phillips

#3 Square Drive Razor Knife Chisel

Cutting will be necessary to complete the kit. Some boards may need to be cut to length. Rough openings for door and window will need to be cut out. Some trim boards may need to be ripped to width.